

ADDENDUM NO. 1
TO THE
DRAWINGS AND SPECIFICATIONS
FOR THE

HENDERSON STREET SIDEWALK PROJECT – THORNTON DRIVE TO MOODY DRIVE
PW 09-06

ISSUED FROM: CITY HALL AT THE SHOWERS BUILDING
Post Office Box 100
401 North Morton Street
Bloomington, Indiana 47404

ISSUE DATE: July 24, 2009

Bid DATE: July 29, 2009

This Addendum No.1, to the drawings and specifications shall supplement, amend and become a part of the bidding documents, plans, and specifications. All bids and construction contracts shall be based on these modifications to the original contract documents.

ITEM No. 1: SHEET C301 – SITE IMPROVEMENT PLAN
A. ALL CAST IRON DOME PLATES SHALL BE DIPPED IN ASPHALTIC COATING BY THE MANUFACTURER.

ITEM No. 2: SHEET C401 – SITE GRADING AND DRAINAGE PLAN
A. ALL EXISTING ASPHALT TO BE REMOVED AS PART OF PROPOSED IMPROVEMENTS SHALL BE REPLACED WIT THE ASPHALT PAVEMENT PATCH SECTION. REFER TO DETAIL No. 6 ON SHEET C601. ALL ROAD WIDENING TO BE CONSTRUCTED PER THE ASPHALT PAVEMENT SECTION. REFER TO DETAIL No. 4 ON SHEET C601.

ITEM No. 3: UNIT PRICE SHEET
A. A REVISED UNIT PRICE SHEED SHALL BE COMPLETED AND SUBMITTED WITH BID DOCUMENTS TO REPLACE THE ORIGINAL UNIT PRICE SHEET WITH ESTABLISHED PRICES FOR ADDITIONS AND DELETIONS.

	 CERTIFIED BY: JUSTIN D. WYKOFF CITY OF BLOOMINGTON STATE OF INDIANA
--	---

Acknowledge receipt of the addendum by submitting a signed copy with your bid proposal.

RECEIVED BY: CONTRACTOR (FIRM AND ADDRESS)

SIGNATURE: _____

DATE: _____

PRINTED NAME: _____

TITLE: _____

Henderson Street Sidewalk – Thornton Drive to Moody Drive

**Supplemental Unit Prices
For
Additions/Deductions**

<u>Item #</u>	<u>Description</u>	<u>Price Each</u>	<u>Unit</u>
1	Topsoil	_____	TON
2	Casting, Adjust to grade	_____	EA
3	Tree Removal, 6" - 10"	_____	EA
4	Tree Removal, 12" - 24"	_____	EA
5	Tree Removal, 26" and Larger	_____	EA
6	Common Excavation	_____	CY
7	Curb, Concrete – 20" Bat. Curb w/8" exposed	_____	LF
8	Sidewalk, Concrete 4" Thick	_____	SY
9	Driveway, Class III (See Detail)	_____	SY
10	Type F Ramp	_____	EA
11	Type G Ramp	_____	EA
12	Type H Ramp	_____	EA
13	Retaining Wall (See Detail)	_____	LF
14	Pavement Repair (city specification)	_____	SY
15	Mulched Seeding	_____	SY
16	Sodding	_____	SY
17	Trees, Northern Red Oak, 2"-3" Cal.	_____	EA
18	12" N-12 Pipe	_____	LF
19	12" C900 Pipe	_____	LF
20	15" N-12 Pipe	_____	LF
21	18" N-12 Pipe	_____	LF
22	24" N-12 Pipe	_____	LF
23	15" RCPA	_____	LF
24	12 inch rip-rap	_____	TON
25	Storm Inlet Type B with Casting	_____	EA
26	Storm Inlet Type E with Casting	_____	EA
27	Storm Inlet Type J with Casting	_____	EA

- **All prices shall reflect complete installation as shown on the plans or stated in the specifications. (Example: Sidewalk includes stone bedding, excavation, Asphalt Pathway includes stone, base, surface and backfill, excavation, etc.)**