

ADDENDUM NO. 1
TO THE
DRAWINGS AND SPECIFICATIONS
FOR THE
SARE-ROGERS RETAINING WALL EXTENSION

ISSUED FROM: CITY HALL AT THE SHOWERS BUILDING
Post Office Box 100
401 North Morton Street
Bloomington, Indiana 47404

ISSUE DATE: August 18, 2015

Bid DATE: August 25, 2015

This Addendum No.1, to the drawings and specifications shall supplement, amend and become a part of the bidding documents, *plans, and specifications*. *All bids and construction contracts shall be based on these modifications to the original contract documents.*

ITEM No. 1: Should Quoters find discrepancies in, or omissions from, the Contract Documents, or should they be in doubt as to their meaning, written notification should be made to the City Engineer. Interpretation of the proposed contract documents will be made only by written addendum. A copy of each addendum will be posted at the City's web site at https://bloomington.in.gov/sections/viewSection.php?section_id=537. The Owner will not be responsible for any other explanations or interpretations of the proposed contract documents.

Q: Mon, Aug 17, 2015 1:23 PM

Please clarify to what extent we are to use the plans uploaded on your site. Certainly there are FAR more proposed improvements on these plans than are needed for this retaining wall extension, and most of which were already installed through the previous INDOT Contract. Please clarify the exact scope needed for this project and/or which notes and improvements from the plans are applicable to this project.

A: The plan section of the plan and profile sheet is provided for reference with the exception of the following;

1. The modular block wall extension is shown in red.
2. Four trees are shown to be moved further up the hill slope.

3. Plan note indicating that 'existing utilities shown on plans are approximated in accordance with available records and physical evidence. Elevations are to be determined by Contractor'.
4. Call out that indicates the slope behind wall ~5:1±.

Project specific information is indicated on the profile section of the plan and profile sheet. The purpose of this project is the erection of a 238 LFT extension of the modular block retaining wall on the northwest corner of Sare and Rogers, relocation of 4 trees, and the installation of 697 SYS of sodding. The profile section of the plan and profile sheet depicts 430 SYS of sodding for the northwest corner of Sare and Rogers. The project will require an additional 267 SYS of sodding on the northeast corner of Sare and Rogers. For the area on the northeast corner, the Contractor shall remove the existing weeds, regrade, and install and roll sodding. The northeast area is defined as an area that is 300 LFT long between the sidewalk and the curbing, as well as, a strip 3 ft wide by 300 ft long along the back side of the sidewalk.

Q: Mon, Aug 17, 2015 1:23 PM

Further, are you going to provide any additional plans for this proposed wall (i.e. over-excavation behind the wall and backfill, what "grade" looks like on top (behind) the wall so we can determine the amount of import fill needed)

A: The selected contractor shall provide shop drawings, stamped by a licensed Engineer, for complete wall systems and all components. Shop drawings for the existing wall have been provided in the Special Conditions section of the quote documents. From which, it is anticipated that 'the proposed wall shall be backfilled with Structural Backfill Type 3 in the reinforced zone and B Barrow in the retained zone'. The Design Engineer has estimated that 200 CYS of barrow will be needed. The finished slope behind the wall shall be graded to meet the top of the wall, and extend upward toward the right-of-way line until it meets the existing grade. As depicted on the plans, the slope behind the wall is approximately 5:1.

Q: Mon, Aug 17, 2015 1:23 PM

Lastly, there is a blanket statement that we are to maintain ALL traffic (vehicular/pedestrian) through this construction site. Are we going to be allowed to store equipment/materials/etc. within the construction site overnight throughout the project, or do you have a nearby staging yard you would allow us to use, or should we include the demobilization and remobilization of ALL items every night & every day?

A: There is a minimal amount of public right-of-way available for staging equipment and materials. This area is located to the north of the proposed wall and between the path and right-of-way line. When needed, and only during working hours, the contractor may close the multi-use path and the western turn lane of South Sare Road. The Contractor shall be responsible for all aspects of the closure, including, but not limited to, the implementation of an ADA complaint Temporary Traffic Control Plan.

	<p>CERTIFIED BY: </p> <p>ANDREW CIBOR, PE, PTOE CITY OF BLOOMINGTON STATE OF INDIANA</p>
--	---

Acknowledge receipt of the addendum by submitting a signed copy with your bid proposal.

RECEIVED BY: CONTRACTOR (FIRM AND ADDRESS)

SIGNATURE: _____ **DATE:** _____

PRINTED NAME: _____

TITLE: _____