

**ADDENDUM NO. 1**  
**TO THE**  
**DRAWINGS AND SPECIFICATIONS**  
**FOR THE**  
**SHEFFIELD DRIVE SIDEWALK PROJECT**

**ISSUED FROM:** CITY HALL AT THE SHOWERS BUILDING  
Post Office Box 100  
401 North Morton Street  
Bloomington, Indiana 47404

**ISSUE DATE:** August 21, 2015

**QUOTE DATE:** August 25, 2015

This Addendum No.1, to the drawings and specifications shall supplement, amend and become a part of the quoting documents, *plans, and specifications*. *All quotes and construction contracts shall be based* on these modifications to the original contract documents.

**ITEM No. 1:** Should Quoters find discrepancies in, or omissions from, the Contract Documents, or should they be in doubt as to their meaning, written notification should be made to the City Engineer. Interpretation of the proposed contract documents will be made only by written addendum. A copy of each addendum will be posted at the City's web site at [https://bloomington.in.gov/sections/viewSection.php?section\\_id=537](https://bloomington.in.gov/sections/viewSection.php?section_id=537). The Owner will not be responsible for any other explanations or interpretations of the proposed contract documents.

**Q:** Mon, Aug 17, 2015 3:27 PM

*Can you please clarify how we are supposed to maintain residents into their drives as they're being removed and replaced? If we can remove all drives and pour them back over the next several days, it would save you considerable \$ rather than to remove and replace 1 per day. This would dictate that the affected residents would have to park somewhere else and would not be able to use their drives until they were poured back. Also, do you require any concrete "cure" time before you want vehicular traffic on them? Typically, folks wait as much as 5 days from the date of the pour to when a car is allowed to traverse the new drive. This would lengthen the time each resident would be inconvenienced and not able to traverse their drive. Please clarify your intentions at your earliest convenience.*

**A:** The Special Condition Section of the quote packet is provided for reference.

Contractor shall coordinate and maintain local access for all residents and local business within the limits of the project before and during construction.

For all maintenance of traffic, including pedestrian routes, the Contractor shall follow the current Indiana Manual on Uniform Traffic Control Devices (IMUTCD) with regard to all signage and signage placement used during the project for both vehicular, bicycle and pedestrian traffic travelling through the project limits. The Contractor shall install and maintain any temporary pedestrian route in accordance with the Draft Public Right of Way Accessibility Guidelines (PROWAG) and must be approved by the Planning and Transportation Department.

Contractor shall limit his/her operations to within the project site, and sod all disturbed areas. Contractors using any property outside the public right of way shall have an agreement in writing from each respective property owner of said property on file with the City of Bloomington Project Representative prior to usage. No verbal agreements are permitted.

Contractor is responsible for securing the construction site at all times.

**A:** The definition of Coordinate:

The synchronization and integration of activities, responsibilities, and command and control structures to ensure that the resources of an organization are used most efficiently in pursuit of the specified objectives. Along with organizing, monitoring, and controlling, coordinating is one of the key functions of management.

**A:** The point that the City is trying to make is it's your responsibility (contractor) to contact the property owners and work with them not ours.

	<p><b>CERTIFIED BY:</b></p> <p>ANDREW CIBOR, PE, PTOE  CITY OF BLOOMINGTON  STATE OF INDIANA</p>
--	--

**Acknowledge receipt of the addendum by submitting a signed copy with your bid proposal.**

**RECEIVED BY: CONTRACTOR (FIRM AND ADDRESS)**

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

**SIGNATURE:** \_\_\_\_\_ **DATE:** \_\_\_\_\_

**PRINTED NAME:** \_\_\_\_\_

**TITLE:** \_\_\_\_\_