



- Notes:
- Where existing concrete sidewalk is to be reconstructed, all disintegrated concrete, brick, stone, or other material shall be completely removed and replaced with new concrete sidewalk in accordance with 604.03. Remove existing sidewalk and restore roadway with 9" 4000 p.s.i concrete and 1 1/2" HMA overlay.
 - Sidewalk shall be constructed to a minimum depth of 4 in. concrete on 4 in. compacted aggregate, and to the width of the adjoining walk. No sidewalk adjacent to the curb shall have a width of less than 6 ft.
 - The removal of concrete sidewalk shall be to uniform lines as directed. The sidewalk to be removed shall be cut in a straight line with an approved power driven concrete saw. The sawing shall be conducted so that the portion of sidewalk to remain in place shall not be damaged. All portions of sidewalk which are damaged shall be replaced.
 - Unless otherwise directed, sidewalk which must be removed shall be removed between tool marks or joints. At locations where the sidewalk and curb are in contact and the curb is deteriorated, the curb shall also be replaced.
 - The new sidewalk shall have a joint pattern similar to the surrounding sidewalk. Sidewalk placed through drives shall be a minimum of 6 in. thick concrete on 6 in. compacted aggregate.
 - All joints adjacent to existing structures must be sealed with silicon joint sealant.
 - Detectable warning elements shall be constructed of cast iron or other City approved material.

- E** INDOT TYPE E RAMP WITH CAST IRON DETECTABLE ELEMENTS SEE E 604-SWCR-09 AND E 604-SWCR-10 FOR DETAILS.
- C** REPLACE CONCRETE CURB.
- D** DEMO / REMOVE EXISTING.

- S4** CONCRETE SIDEWALK, 4 IN. ON 4 IN. COMPACTED AGGREGATE.
- JF** PREFORMED JOINT MATERIAL, 1/2 IN.
- TG** ADJUST CASTING TO GRADE.
- P** PAVEMENT PATCH

RECOMMENDED FOR APPROVAL _____	
CITY ENGINEER DATE	
DESIGNED: _____	DRAWN: REA
CHECKED: _____	CHECKED: _____

**CITY OF BLOOMINGTON
ENGINEERING DEPARTMENT**

E 3RD STREET AND S CLARIZZ BLVD
NORTH CURB RAMPS

HORIZONTAL SCALE 1" = 5'	BRIDGE FILE
VERTICLE SCALE	DESIGNATION
SURVEY BOOK	SHEETS
CONTRACT	1 of 1 PROJECT