

ADDENDUM NO. 2

TO THE

DRAWINGS AND SPECIFICATIONS

FOR THE

WINSLOW-HENDERSON PATH AND INTERSECTION IMPROVEMENTS PROJECT

ISSUED FROM: The City of Bloomington
Planning and Transportation Department
Post Office Box 100
401 North Morton Street, Suite #130
Bloomington, Indiana 47402

Issue Date: June 7, 2019

Letting Date: June 10, 2019

This Addendum No.2 to the drawings and specifications shall supplement, amend and become a part of the bidding documents, plans, and specifications for the Winslow-Henderson Path and Intersection Improvements Project. All bids and construction contracts shall be based on these modifications to the original contract documents. Bidders shall acknowledge receipt of this Addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

Item No. 1: As depicted in the Special Conditions of the Bidding Documents, 'Clearing Right of Way', all removal and excavation task shall be paid for under the unit pay item 'CLEARING RIGHT OF WAY'. This work shall include, but not be limited to, the removal of any existing headwalls, retaining walls, concrete curb, curb and gutter, concrete steps, paved side ditches, sidewalks, guardrails, and common excavation. Lines 4, 5, 6, 7, 8, 9, and 19 have been removed from the Proposed Schedule of Items (Unit Prices). All bidders shall use with their submitted bids the revised Unit Price sheet included with this Addendum.

Item No. 2: The Contractor shall verify the dimensions for the headwall for Structure No. 14 with site conditions, handrail installation, and pipe installation. The cost of the headwall construction for Structure No. 14, including but not limited to all design, materials, and installation shall be included in the cost of PIPE EXTENSION, ELLIPTICAL, 2.75' X 4.25'. The handrail for Structure No. 14 will be paid for as HANDRAIL, PEDESTRIAN AND BICYCLE.

CERTIFIED BY: _____

NEIL KOPPER

INTERIM ENGINEER

CITY OF BLOOMINGTON, IN

Acknowledge receipt of this addendum No. 2 by representing it on the Bid form in Section B and submitting a signed copy with your bid proposal.

RECEIVED BY: CONTRACTOR (FIRM AND ADDRESS)

SIGNATURE: _____

DATE: _____

PRINTED NAME: _____

TITLE: _____



**City of Bloomington
Planning and Transportation Department**

Letting Date: June 10, 2019

Proposal Schedule of Items (Unit Prices)

Project Title : Winslow Rd. and Henderson St. Path Project

LINE	INDOT CODE	DESCRIPTION	Estimated Quantities	UNITS	UNIT PRICE	BID AMOUNT
001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS	-	-
002	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS	-	-
003	201-52370	CLEARING RIGHT OF WAY	1.00	LS	-	-
004	202-02278	CURB, CONCRETE, REMOVE	622.00	LFF	\$0.00	\$0.00
005	202-02279	CURB AND GUTTER, REMOVE	175.00	LFF	\$0.00	\$0.00
006	202-03875	CONCRETE STEPS, REMOVE	9.40	SYS	\$0.00	\$0.00
007	202-02272	PAVED SIDE DITCH, CONCRETE, REMOVE	11.50	SYS	\$0.00	\$0.00
008	202-52710	SIDEWALK, CONCRETE, REMOVE	856.00	SYS	\$0.00	\$0.00
009	203-02000	EXCAVATION, COMMON	826.00	CYD	\$0.00	\$0.00
0010	205-06933	TEMPORARY INLET PROTECTION	11.00	EA	-	-
0011	205-06937	TEMPORARY SILT FENCE	54.00	LFT	-	-
0012	207-08264	SUBGRADE TREATMENT, TYPE II	381.00	SYS	-	-
0013	207-08266	SUBGRADE TREATMENT, TYPE III	2364.00	SYS	-	-
0014	207-09935	SUBGRADE TREATMENT, TYPE IC	65.00	SYS	-	-
0015	211-09264	STRUCTURE BACKFILL, TYPE 1	120.00	CYD	-	-
0016	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	595.00	TON	-	-
0017	304-07491	HMA PATCHING, TYPE C	30.00	TON	-	-
0018	406-05521	ASPHALT FOR TACK COAT	193.00	SYS	-	-
0019	601-02241	GUARDRAIL, REMOVE	75.00	LFF	\$0.00	\$0.00
0020	604-05528	HMA FOR SIDEWALK	311.00	TON	-	-
0021	604-06070	SIDEWALK, CONCRETE	266.00	SYS	-	-
0022	604-08086	CURB RAMP, CONCRETE	106.00	SYS	-	-
0023	604-44251	CONCRETE STEP	6.40	SYS	-	-
0024	604-95344	HANDRAIL, PEDESTRIAN	16.50	LFT	-	-
0025	604-95344	HANDRAIL, PEDESTRIAN AND BICYCLE	24.00	LFT	-	-
0026	605-06120	CURB, CONCRETE	737.00	LFT	-	-
0027	605-06125	CURB, CONCRETE, MODIFIED	98.00	LFT	-	-
0028	605-06140	COMBINED CURB & GUTTER, CONCRETE	603.00	LFT	-	-
0029	605-06215	CENTER CURB, D, CONCRETE	2.00	SYS	-	-
0030	610-07488	HMA FOR APPROACHES, TYPE C	29.00	TON	-	-
0031	610-09108	PCCP FOR APPROACHES, 9"	381.00	SYS	-	-
0032	616-02320	GEOTEXTILES	54.00	SYS	-	-
0033	616-06451	RIPRAP, UNIFORM	53.00	TON	-	-
0034	618-04181	BICYCLE RACK	1.00	EA	-	-
0035	621-02770	EROSION CONTROL BLANKET	254.00	SYS	-	-
0036	621-06575	NURSERY SOD	1841.00	SYS	-	-
0037	628-09401	FIELD OFFICE, A	6.00	MOS	\$0.00	\$0.00

Continued to next page



**City of Bloomington
Planning and Transportation Department**

Letting Date: June 10, 2019

Proposal Schedule of Items (Unit Prices)

Project Title : Winslow Rd. and Henderson St. Path Project

LINE	INDOT CODE	DESCRIPTION	Estimated Quantities	UNITS	UNIT PRICE	BID AMOUNT
0038	715-05149	PIPE, TYPE 2, CIRCULAR 12"	170.00	LFT	-	-
0039	715-05152	PIPE, TYPE 2, CIRCULAR 18"	106.00	LFT	-	-
0040	715-05152	PIPE, PVC, 4"	32.00	LFT	-	-
0041	715-05152	PIPE, PVC, 10"	5.00	LFT	-	-
0042	715-05422	PIPE, SLOTTED DRAIN, 12"	76.00	LFT	-	-
0043	715-05756	PIPE EXTENSION, CIRCULAR, 12"	5.00	LFT	-	-
0044	715-07251	PIPE EXTENSION, ELLIPTICAL, 2.75' X 4.25'	24.00	LFT	-	-
0045	715-46000	PIPE END SECTION, 12"	1.00	EA	-	-
0046	715-46010	PIPE END SECTION, 18"	1.00	EA	-	-
0047	720-44000	CASTING, ADJUST TO GRADE	4.00	EA	-	-
0048	720-04790	CASTING, REMOVE AND REPLACE	1.00	EA	-	-
0049	720-45410	MANHOLE, C4	1.00	EA	-	-
0050	720-98174	INLET, TYPE B-15	2.00	EA	-	-
0051	720-98555	INLET, TYPE C-15	4.00	EA	-	-
0052	801-06775	MAINTAINING TRAFFIC	1.00	LS	-	-
0053	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED BASE	66.00	LFT	-	-
0054	802-07060	SIGN, SHEET, RELOCATE	5.00	EA	-	-
0055	802-09838	SIGN, SHEET WITH LEGEND, 0.08" THICKNESS	7.50	LFT	-	-
0056	805-02150	PEDESTRIAN SIGNAL INDICATION, 18"	2.00	EA	-	-
0057	805-11817	PEDESTRIAN PUSH BUTTON AND SIGN, APS	2.00	EA	-	-
0058	805-78470	SIGNAL CABLE ROADWAY LOOP COPPER 1C/14GA	496.00	LFT	-	-
0059	805-78485	SIGNAL CABLE, 5C/14GA	548.00	LFT	-	-
0060	805-78785	SIGNAL DETECTOR HOUSING	1.00	EA	-	-
0061	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALANT	162.00	LFT	-	-
0062	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 24"	610.00	LFT	-	-
0063	808-06703	LINE, THERMOPLASTIC, WHITE, SOLID, 4"	441.00	LFT	-	-
0064	808-06716	LINE, REMOVE	2428.00	LFT	-	-
0065	808-75245	LINE, THERMOPLASTIC, YELLOW, SOLID, 4"	1944.00	LFT	-	-
0066	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24"	79.00	LFT	-	-
0067	808-75320	TRANSVERSE MARKINGS, THERMO, LANE INDICATION ARROW	4.00	EA	-	-
0068	801-06775	MAINTAINING TRAFFIC	1.00	LS	\$0.00	\$0.00
TOTAL PROJECT BID:					-	-

Bidder acknowledges that:

- Each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and
- estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all Unit Price Work will be based on actual quantities, determined as provided in the Contract Documents.